

Overpass of 500 meters



Description

For this overpass, Holcon provided the engineering, production and assembly of the prefab concrete. In addition, also the supply of bearing blocks, prestressing and the reinforcement of the pressure layers. The overpass is approximately 25 meters x 500 meters. For this purpose, among other things, 375 rail girders, 30 bottom girders of 80...

Contractor

BAM